Sl. No.	Items of work	Per	Quantity
18	Teakwood doors 1¼″ thick with panelled shutters with iron clamps, iron works such as hinges, tower bolts, pad-locks, etc., complete.	S.ft.	114
19	Teakwood doors, 1½″ thick with battened shutters, with four folded iron clamps, hinges, tower bolts, pad locks, etc., complete. The side frame to be fixed in cill slab in 3″ depth to fix the frame.	,,	44
20	Teakwood windows with expanded metal one inch mesh quarter inch thick outside fixed, inside glazed shutters with iron bars ¾″ dia. fastenings, hinges, etc., complete to Sub-Registrars' Clerks' and record rooms.	,,	95
21	Teakwood windows with panelled shutters outside and inside glazed ¾″ dia. iron bars with iron clamps, hinges, etc., complete.	,,	157
22	Teakwood ventilators with expanded metal of one inch mesh and quarter inch thick, the shutters fixed to frame and iron bars and clamps, etc., complete.	,,	21
23	Teakwood finials at gable ends 4′ long 4″×4″ ...	No.	2
24	Silicate chocolate paint	Sqr.	12·84
25	Flooring with 1½″ thick Cuddapah slabs over 3″ concrete bed and cement pointing.	,,	12·06
26	Flooring with burnt stone slabs, 4½″×6″ thick over 6″ sandbed and cement pointing to spirit room.	,,	2·64
27	Expanded metal (1″ mesh and ¼″ thick) partition with four folded shutters with teak frame 2″×3″ with four partitions in height painting, etc., complete.	S.ft.	135
28	Teakwood screen with double shutters, wooden panel, filling, fixed in floor, iron work and painting, etc., complete.	,,	84
29	Teakwood terminal finials	No.	4
30	Zinc storm water drain pipes 3″ dia. built into masonry.	R.ft.	112
31	Tarring wood work	Lump sum	
32	Providing Clerestories top and spirit room ...	Lump sum	
33	Clearing site and levelling ground and forming ramp in the side of verandah and spirit room.	Lump sum	

V. V. PATANKAR,
Executive Engineer.

MYSORE DIVISION.

Notice dated 19th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division up to 10th January 1928, for constructing a building for the New Police Station at Mandya. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the houre of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompained by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

r must be accompained by a deposit of Rs. 200 only in cash or sory Notes, as earnest money and be superscribed "Tender for construc- for the New Police Station at Mandya" in default of which, tenders will

cceptance of any tender will rest with the Executive Engineer, who does ccept the lowest or any tender or to assign any reason whatever for the ler.

ht days of the acceptance of the tender, the successful competitor execute the usual contract bond, in default of which his tender ncelled, and his earnest money will be forfeited.

of the successful competitor, whose tender has been accepted, will otice Board in the Executive Engineer's Office in due course. No the acceptance or rejection of a tender will receive any reply.

nce of one of the tenders, the earnest money on rejected tenders will be

act estimate for Constructing a Police Station at Mandya.

Items of work	Per	Rate	Quantity	Cost	Total
		Rs. a. p.			Rs.
excavation	C.yd.	0 4 0	29	8	
k in chunam	C.ft.	0 5 0	1788	559	
in mud	,,	0 3 6	1928	422	
e slabs dressed	S.ft.	0 12 0	189	142	
with chunam	Sqr.	4 0 0	36·15	144	
colour washing... ..	,,	0 6 0	36·15	13	
r compound wall ...	R.ft.	0 4 0	61	15	
door battened	S.ft.	1 12 0	69	121	
lock-up door	,,	3 8 0	36	126	
windows with iron bars, etc.	,,	2 0 0	8	16	
ventilators do ...	,,	1 12 0	7	12	
wrought and put up ...	C.ft.	6 0 0	57·57	345	
ith first class Mangalore tiles	S.ft.	35 0 0	11·64	407	
eepers, etc.					
s set in mortar	R.ft.	0 12 0	40	30	
g tiles	Each	3 0 0	4	12	
painting	Sqr.	4 0 0	2·39	10	
drain with slab over cement ng.	R.ft.	0 14 0	100	88	
eave board	,,	0 12 0	140	105	
ood railing with way and ing.	,,	0 14 0	57	50	
ground and clearing site ...	Lump	Sum	...	10	
ood work	,,	,,	...	5	
ing steps in latrine and cement ing.	,,	,,	...	5	
with Cudapah slabs on 3" cete bed and cement pointing.	Sqr.	35 0 0	5·45	190	
ceiling for lock-up ...	,,	10 0 0	2·30	23	
Total		...	...	...	2,858
Contingencies		...	...	...	142
Grand Total		...	...	...	3,000

Dated 20th December 1927.

eby given that sealed tenders will be received at the Office of the Executive Division, up to 10th January 1928, for constructing a Local Fund Dispen- njangud Taluk. An approximate estimate of quantities is given below.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees two hundred only (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Local Fund Dispensary at Hura, Nanjangud Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Local Fund Dispensary at Hura, Nanjangud Taluk, without houses:—

Sl. No.	Items of work	Per	Rate	Quantity	Cost	Total
	MAIN BUILDING.		Rs. a. p.		Rs.	
1	Earthwork excavation	C.yd.	0 4 0	74	19	
2	Brick in mortar	C.ft.	0 4 0	4,999	1,250	
3	Brick in mortar arch work	,,	0 8 0	99	50	
4	Burnt stone slabs 6" thick and dressed ...	S.ft.	0 12 0	350	262	
5	Cut stone pillars with capitals and bases, complete.	Each	30 0 0	10	300	
6	Masonry mouldings at ends	,,	4 0 0	2	8	
7	Plastering with mortar	S.qr.	4 8 0	39·26	177	
8	Whitewashing	,,	0 5 0	23·39	7	
9	Teakwood panelled doors without bottom rail, hinges, etc., complete.	S.ft.	2 8 0	126	315	
10	Colour washing	Sqr.	0 6 0	15·87	6	
11	Teak wood windows with iron bars of ¾" dia panelled, hinges, etc., complete and glazed shutters.	S.ft.	2 8 0	82	205	
12	Ventilators (teakwood) with glazed shutters	,,	1 8 0	27	41	
13	Teakwood circular ventilators	,,	4 0 0	13	52	
14	Teakwood wrought and put up ...	C.ft.	4 8 0	115·72	521	
15	Roofing with 1st class Mangalore tiles over teak reapers, etc., complete.	Sqr.	37 0 0	19·20	710	
16	Ridge tiles set in mortar and cement pointing.	R.ft.	1 0 0	80	80	

Sl. No.	Items of work	Per	Rate	Quantity	Cost	Total
			Rs. a. p.		Rs.	Rs.
17	Zinc sheets for valley	S.ft.	1 0 0	44	44	
18	Teakwood planks ½" thick	„	0 8 0	44	22	
19	Eave boards 9" high, ornamental ...	R.ft.	0 14 0	262	229	
20	Cornice 3" complete	„	0 8 0	25	13	
21	Wood oiling two coats	Sqr.	3 0 0	18·15	54	
22	Chacolate painting	„	6 0 0	8·89	53	
23	Teakwood finials	Each	3 0 0	4	12	
24	Teakwood shelf plank 1½' thick ...	S.ft.	1 8 0	87	131	
25	Flooring with 9" square Mangalore tiles over 3" concrete and cement pointing.	Sqr.	37 0 0	4·29	159	
26	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	„	37 0 0	4·61	170	
27	Constructing cisterns	Each	5 0 0	2	10	
28	Clearing site		Lump sum			
	Total ...	...	..	...	..	4,910
	KITCHEN.					
1	Earthwork excavation	C.yd.	0 4 0	4	1	
2	Brick in clay	S.ft.	0 4 0	454	114	
3	Burnt stone slabs 6" thick and dressed ...	„	0 12 0	28	17	
4	Plastering with chunam	Sqr.	4 8 0	5·88	26	
5	White and colour washing	„	0 5 5	5·88	2	
6	Teakwood battened door, complete ...	S.ft.	2 0 0	18	36	
7	Teakwood windows with (battened) iron bars complete.	„	2 4 0	4½	10	
8	Teakwood wrought and put up ...	C.ft.	4 8 0	8·01	36	
9	Roofing with 1st class Mangalore tiles over teak reapers.	S.ft.	37 0 0	2·29	85	
10	Ridge tiles set in mortar and cement pointing	R.ft.	1 0 0	15	15	
11	Teakwood eave board (plain) 6" high ..	„	0 8 0	60	30	
12	Wood oiling two coats	Sqr.	3 0 0	0·74	2	
13	Chacolate painting two coats	„	6 0 0	1·05	6	
14	Flooring with Cuddapah slabs over 3" concrete and cement pointing	„	37 0 0	0·32	12	
15	Constructing oven and cistern		Lump sum		5	
16	Ventilating tiles for kitchen	Each	3 8 0	4	14	
	Total ...	...	...	...	...	4
	LATRINE.					
1	Earthwork excavation	C.yd.	0 4 0	4	1	
2	Burnt brick in mortar	C.ft.	0 4 0	362	91	
3	Coping with burnt brick in mortar and plastering, complete.	R.ft.	0 8 0	40	20	
4	Plastering with mortar	Sqr.	4 8 0	426	19	
5	Tarring	„	2 0 0	1·08	2	
6	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	„	37 0 0	0·63	23	
	Total ...	...	...	...	...	
	Grand Total Rupees ...	...	...	...	...	

L. A. H. WIR(EL
Executive Eng

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 (rupees two hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Haluvagal-Makankatte, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantity for restoring Haluvagal-Makankatte Registered No. 112, Hassan Taluk.

No.	Details of work	Per	Quantity
	Bund at R. L. 56·00.		
1	Earthwork to bund including consolidation	C.yd.	2860
2	Rough stone work, new	„	949
3	Do old with new jelly	„	26
4	Turfing	S.yd.	4009
5	Cleaning jungle	Lump sum	
6	Cutting grips	Each	17
7	Providing grade and index stones	„	17
8	Register number and constructive details stones ...	„	1
9	Gauge stone	„	2
	Constructing sluice at R. L. 41·00.		
1	Earthwork excavation cutting bund and refilling, etc., including exravation in rock.	Lump sum	
2	Concrete in surki mortar	C.ft.	498
3	Burnt brick in surki mortar	„	744
4	Do archwork	„	257
5	Do stone slabs 6" thick	S.ft.	56
6	Do do 8" „	„	299
7	Plastering with surki mortar	Sqr.	5·00
8	Providing teakwood plug, etc.	Lump sum	
9	Cutting and upper and lower orifices	Do	
	Constructing a Regulation & B in sluice channel.		
1	Earthwork excavating, etc.	T—	
2	Concrete in surki mortar ...		
3	Burnt brick in surki —		

No.	Details of work	Per	Quantity
	Constructing Right waste weir 355' long at R. L. 50·00.		
1	Earthwork excavating foundation partly gravel and partly soft rock.	C.yd.	333
2	Burnt brick in surki mortar	C.ft.	10580
3	Plastering with do	Sqr.	27·00
4	Stone slabs 6" thick	S.ft.	1067
5	Rough stone work	C.yd.	392
6	Jelly bocking to apron	"	231
7	Draft clearing	"	920
	Constructing a left waste weir 120' long at R. L. 50·00.		
1	Earthwork excavation in soft rock	C.yd.	220
2	Concrete in surki mortar	C.ft.	473
3	Burnt brick in do	"	1149
4	Plastering in do	Sqr.	8·00
5	Stone slabs 6" thick	S.ft.	585
6	Rough stone work	C.yd.	185
7	Removing and resetting old apron	Lumpsum	
8	Providing shutters to regulator at A	Do	
	Improving lifting dam across Kodihalla.		
1	Earthwork excavation	C.yd.	22
2	Burnt brick in surki mortar	C.ft.	1248
3	Plastering in do	Sqr.	2·77
4	Rough stone work, new	C.yd.	108
5	Do using old stone	"	74
6	Clearing slush and removing silt blocking up water way ...	Lumpsum	
	Improving the feeder channel.		
1	Earthwork cutting and forming into bank	C.yd.	4753
2	Rough stone in mortar	C.ft.	188
3	Do work (new)	C.yd.	7
4	Revetting sides of channel at sites of breaches	Lumpsum	
5	Providing two stone work pipe sluices in channels ...	Do	

R. L. STEELE.
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

The attention of the public is invited to the notice of calling for tenders for constructi a girder bridge across Nallur Halla on Shimoga-Mangalore Road, *vide* page 1086 and 10 of the *Mysore Gazette* dated 15th November 1927.

M. A. SRINIVASACHARI,
Executive Engineer

CHITALDRUG DIVISION.

FORM OF ADVERTISEMENT.

Dated 23rd December 1927.

Notice is hereby given that sealed tenders will be received at the office of the Execu Engineer, Chitaldrug Division, up to 31st January 1928, for constructing a Town Building at Harihar, Harihar Sub-Taluk. An approximate estimate of quantities is g below. These quantities are not guaranteed. The work should be completed by the e

and conditions may be seen at the Executive Engin